

ITEM	DESCRIPTION OF WORKS	QTY	UNIT	RATE	AMOUNT
	<p><u>ELEMENT NO. 04 - WALLING</u></p> <p><u>HEAVY DUTY ALUMINIUM ALLOY PANELS</u></p> <p><u>Supply and fix Anodized Aluminium Profile framing ex-UAE 100mm × 45mm ×1.2mm thick.</u></p> <p><u>Infill 10mm thick clear laminated complete with all fittings and accessories all necessary iron mongery.</u></p>				
A	Panels	70	M ²		
B	Supply and fix MdF sheets fixed with aluminium profile size 100mm complete with all accessories, colour approved with Architects.	492	M ²		
ELEMENT NO. 04 - WALLING CARRIED TO SUMMARY OF BILL NO. 03					-

ITEM	DESCRIPTION OF WORKS	QTY	UNIT	RATE	AMOUNT
	<p><u>ELEMENT NO. 05 - DOORS</u></p> <p><u><i>Supply and fix Alluminium doors with associate accessories</i></u></p> <p>A Overall size 2700x2400mm high</p> <p>B Overall size 2400x2400mm high</p> <p>C Overall size 800x2400mm high</p>	<p>1</p> <p>2</p> <p>13</p>	<p>No</p> <p>No</p> <p>No</p>		
ELEMENT NO. 05 - DOORS CARRIED TO SUMMARY OF BILL NO. 03					-

ITEM	DESCRIPTION OF WORKS	QTY	UNIT	RATE	AMOUNT
A	<p><u>ELEMENT NR.1: DEMOLITION AND ALTERATIONS</u></p> <p>Carefully demolish the existing mdf sheet and prepare the surface for new works and remove all debris away from site (approx 596 m²)</p>		Item		
	DEMOLITION CARRIED TO BILL NO 3				-

SUMMARY

ELEMENT	DESCRIPTION	AMOUNT (TSHS)
1	WALLING	
2	DOORS	
	BILL No 03 - MEASURED WORKS CARRIED TO GENERAL SUMMARY	-

ITEM	DESCRIPTION OF WORK	QTY	UNIT	RATE	AMOUNT
	<p><u>BILL NR.2 - PC & PROVISIONAL SUMS</u></p> <p><u>PRIME COST SUMS</u></p> <p><i><u>The following provisional sums are for the works or costs which can not entirely be foreseen, defined or detailed during the preparation of Bills of Quantities and should be used in whole or in part at the discretion of the Architect:</u></i></p> <p>A Provide sum to cover electrical works</p> <p>B Provide sum to cover plumbing works</p>		Sum sum		
	BILL NR. 2 – PC & PROVISIONAL SUMS CARRIED TO				-

GENERAL SUMMARY

S/No	DESCRIPTION OF WORK	AMOUNT
1	BILL NR. 01: DEMOLITION	
2	BILL NR. 02: PRIME COSTS AND PROVISIONAL SUMS	10,500,000.00
3	BILL NR. 03: MEASURED WORKS	
	<p align="right">SUB-TOTAL-1</p>	
	<p>CONTINGENCY 3%</p> <p align="right">SUB-TOTAL-2</p>	
	<p><u>Condition of contract Clause 13</u></p> <p>Allow for the cost of insurance in the joint names of the Employer and contractor, against loss or damage to the Works, plants, materials, equipment etc.</p> <p><u>Condition of contract clause 54</u></p> <p>Allow for cost of providing performance security for 10% of the contract sum</p> <p align="right">SUB-TOTAL-3</p>	
	<p>ADD: 18% Value Added Tax(VAT)</p> <p align="right">SUB-TOTAL-4</p>	
	<p align="center">FIXED PRICE CARRIED TO FORM OF TENDER</p>	